

CITY OF LAKEPORT

ADDENDUM NO. 1  
LAKESHORE BOULEVARD ER PROJECT  
FROM SAYRE ST TO JONES ST  
BID NO. 16-03

Bid Opening: August 24, 2016 at 2:00 PM  
Issued Date: August 17, 2017

The following revisions are hereby made to the above referenced project:


1. Revise the first paragraph of Section 72, "SLOPE PROTECTION" as follows:  

Geocell: Geocell shall be GeoWeb GW20V-8 Inch depth by Presto Geosystems;  
EnviroGrid EGA 20 w/ 8 inch deep cells by Geo Products, or equal approved by  
the Engineer prior to bid. The geocell walls shall be textured.
2. Insert revised Bid Schedule (Item 9 – Contractor-Supplied Biologist is delete. No Contractor supplied biologist required on project).
3. The attached Pre-bid Meeting Notes are attached and are part of the contract requirements.
3. The bid date remains unchanged.

All questions regarding this project shall be transmitted in writing to Doug Grider or Kevin Ingram as indicated in the bid documents.

Pleas indicate receipt of this addendum on the proposal at the location indicated. Failure to do so may cause rejection of your bid.

Approved:



Kevin Ingram  
Community Development Director

**CONTRACTOR'S BID**

**LAKESHORE BOULEVARD  
ER PROJECT  
FROM SAYRE ST TO JONES ST**

**BID NO. 16-03  
Addendum No. 1 – August 17, 2016**

**BASE BID**

<b>Item No.</b>	<b>Description</b>	<b>Estimated Quantity</b>	<b>Unit of Measure</b>	<b>Unit Price (In Figures)</b>	<b>Total (In Figures)</b>
1	Mobilization	Lump Sum	LS		
2	Construction Site Management	Lump Sum	LS		
3	Prepare Water Pollution Control Plan	Lump Sum	LS		
4	Water Pollution Control	Lump Sum	LS		
5	Erosion Control	Lump Sum	LS		
6	Construction Staking	Lump Sum	LS		
7	Construction Area Signs	Lump Sum	LS		
8	Traffic Control System	Lump Sum	LS		
9	Item Deleted	n/a	n/a		
10(F)	Excavation & Removal	1,065	CY		
11(F)	8 Inch Geocell	15,900	SF		
12(F)	3/4 Inch Class 2 Aggregate Base	842	TON		
13(F)	Rock Slope Protection (No. 2, Method B)	500	TON		
14(F)	Rock Slope Protection (1/2 T Method A)	809	TON		
15	Concrete Curb	41	LF		
16	Concrete Curb & Gutter	58	LF		
17	Under Sidewalk Drain	3	EA		
18	6 Inch Hot Mix Asphalt Digout	388	SF		
19(F)	Willow Shoot Planting	690	EA		
<b>BASE BID TOTAL:</b>					
<b>ADDITIVE ALTERNATE BID</b>					
20(F)	Rock Slope Protection (2T, Method A)	150	TON		
21	Hot Mix Asphalt (Type A)	30	TON		
<b>ADDITIVE ALTERNATE TOTAL:</b>					

**Project shall be awarded based on the Base Bid Amount**

Lakeshore ER Project  
BID NO. 16-03  
Pre-bid Meeting Notes  
7/26/2016

1. There is a bid item of planting willow trees in the final rip rap.
2. The bid item for a biologist will be deleted.
3. Contractor shall cut weeds and vines as part of clearing and grubbing. *(This is slightly different than discussed on site).*
4. The lake level is anticipated to be out of the construction zone at scheduled start date.
5. All debris will be stockpiled at the city yard on Hwy 175. Concrete and asphalt needs to be separated from any excavated soils.
6. There is a restriction that no more than 100' of bank be exposed from excavation to placement of No. 2 crushed rock (phase 2 of 3 layer system) at any time.
7. There is a bid alternative to place 2 ton rocks. Bid will be awarded from base bid.
8. Pre-bid meeting notes shall be included in the first Addendum.
9. A reminder that this is a federally funded project with DBE Goals with all the required documentation. Be extra careful with bid submission paperwork.