

DOWNTOWN IMPROVEMENT PROJECT – PHASE II
BID NO. 16-01
IN THE CITY OF LAKEPORT, CALIFORNIA
BID SCHEDULE
(Addendum No. 3)

The cost of all labor, services, material, equipment and installation necessary for the completion of the work itemized under this schedule, even though not shown or specified, shall be included in the unit price for the various items shown herein. For a description of the work associated with each bid item, see **SECTION E–SPECIAL PROVISIONS**. The Agency reserves the right to increase or decrease the quantity of any item or omit items as may be necessary, and the same shall in no way affect or void the contract, except that appropriate additions or deductions from the contract total price will be made at the stipulated unit price in accordance with these Contract Documents.

The Agency reserves the right to reject any and all bids, to waive any informality in a bid, and to make awards in the interest of the Agency.

The Contractor shall perform an independent take-off of the plans and bid accordingly. Quantities listed in this Bid Schedule are intended only as a guide for the Contractor as to the anticipated order of magnitude of work. The Contractor shall be responsible for verifying all estimated quantities. The Contractor will be reimbursed for the quantity of items actually installed as required by the Contract Documents, including addenda, and shown on the plans to neat line and grade.

The Contractor will not be reimbursed for work performed for his convenience, or as required to adapt to field conditions, or for unauthorized work performed outside of that required by the Contract Documents.

The Contractor shall be responsible for calculating and providing totals for the bid schedule. The proposal schedule shall include all costs for labor, services, material, equipment, and installation associated with completing the work in place per the plans, specifications and details.

NAME OF BIDDER: _____
CONTRACTOR’S LICENSE NO.: _____
AUTHORIZED SIGNATURE: _____
TITLE: _____
DATE: _____

The Contract will be awarded on the Base Bid Amount.

DOWNTOWN IMPROVEMENT PROJECT – PHASE II
BID NO. 16-01
IN THE CITY OF LAKEPORT, CALIFORNIA
BID SCHEDULE
(Addendum No. 3)

DOWNTOWN IMPROVEMENT PROJECT PHASE II					
Base Bid Schedule (Addendum 3)					
ITEM	DESCRIPTION	UNIT	QTY	UNIT PRICE	COST
1	Mobilization	LS	1		
2	Traffic & Pedestrian Control System	LS	1		
3	Pothole Existing Utilities	LS	1		
4	Erosion Control & SWPPP	LS	1		
5	Construction Staking	LS	1		
6	Sheeting, Shoring, Bracing	LS	1		
7	Remove, Salvage, Store and Reset Bus Shelter	EA	1		
8	Remove, Salvage, Store and Reset Memorial Plaques	EA	26		
9	Remove and Salvage Signs and Street Furniture	LS	1		
10	All Other Demolition	LS	1		
11	Concrete Sidewalk - Standard Grey	SF	19357		
12	Concrete Sidewalk - Stamped and Colored	SF	1948		
13	Raised Concrete Sidewalk	SF	348		
14	Truncated Domes	SF	343		
15	Concrete Vertical Curb - Type A1-6"	LF	55		
16	Concrete Curb and Gutter - Type A2- 18"	LF	2031		
17	Sidewalk Drain	EA	9		
18	3" Cold Plane	SF	60199		
19	6 " Remove and Replace HMA in Travel Lanes	SF	8528		
20	6 " Remove and Replace HMA in Trench Patches	SF	5053		
21	3" Remove and Replace HMA in Misc. Locations	SF	3916		
22	No. 4 HMA (leveling)	TON	482		
23	1/2 HMA (surface)	TON	869		
24	Pavement Interlayer	SF	48900		
25	Street Print HMA Stamp and Color	SF	5908		
26	Construct Vent Box	EA	12		
27	Tree Frame and Grate	EA	34		

DOWNTOWN IMPROVEMENT PROJECT – PHASE II
BID NO. 16-01
IN THE CITY OF LAKEPORT, CALIFORNIA
BID SCHEDULE
(Addendum No. 3)

28	Provide Flagpole Mount	EA	29		
29	Remove, Salvage, Store and Reset Trash Receptacles	EA	12		
30	Install New Trash Receptacles	EA	4		
31	Handrail	If	111		
32	Thermoplastic Traffic Stripe (4")	LF	2025		
33	Thermoplastic Pavement Markings	SF	2316		
34	New Single post Sign with Panel	EA	39		
35	72" Storm Drain Manhole	EA	1		
36	Curb Inlet, Type GOL-10 w/Type 24x Frame & Grate	EA	4		
37	Curb Inlet, Type GO w/Type 24X Frame & Grate	EA	3		
38	36"x36" SD Junction Box	EA	1		
39	23" x 14" Class 5 Elliptical RCP	LF	280		
40	Modify Storm Drain Manhole/DI	EA	6		
41	6" Sanitary Sewer drop connection	EA	4		
42	Reset Manhole Frame and Grates	EA	15		
43	Reset 6" Sanitary Sewer Rodding Inlet, SSCO or Abandon Rodding Inlet	EA	4		
44	6" PVC (SD-26) Sanitary Sewer Main	LF	1025		
45	Red Curb Markings	LF	1200		
46	Remove 48" Sanitary Sewer Manhole	EA	3		
47	4" Sanitary Sewer Lateral (shallow), Cleanout & Box	EA	23		
48	4" Sanitary Sewer Lateral (deep), Cleanout & Box	EA	7		
49	6" Sanitary Sewer Lateral (shallow), Cleanout & Box	EA	1		
50	DELETED				
51	4" Gate Valve & Box	EA	3		
52	6" Gate Valve & Box	EA	9		
53	8" Gate Valve & Box	EA	7		
54	1" Water Service (single) & Box	EA	14		
55	2" Water Service (single) & Box	EA	1		
56	2" Water Service (double) & Box	EA	2		
57	1" Pressure reducing Valve & Box	EA	5		
58	Reset Fire Hydrant	EA	3		
59	Quad 1" Water Services with 2" lateral and 2 Boxes	EA	2		
60	Double 1" Pressure Reducing Valves and Box	EA	1		
61	1" Water Services Stub & Box	EA	1		
62	Reconstruct Fire Hydrant	EA	1		
63	Relocate Street Lights & Install New Bases and Pull Boxes	EA	27		

DOWNTOWN IMPROVEMENT PROJECT – PHASE II
BID NO. 16-01
IN THE CITY OF LAKEPORT, CALIFORNIA
BID SCHEDULE
(Addendum No. 3)

64	Modify/Extend Street Light Conduit & Install New Conductors	LS	1		
65	New Service, Panels, and Controls	EA	1		
66	Install New Street Lights, Bases, & Pull Boxes	EA	3		
67	Conduit for Tree Receptacles	LS	1		
68	Electrical Outlet and Pigtails at Tree Well	EA	34		
69	Install Conductors for Tree Well Receptacles	LS	1		
70	Controller, wall mount in vandal-resistant enclosure	EA	1		
71	Install Tree including all features	EA	34		
72	Maintenance Period, 6 month	MO	6		
73	Controller, wall mount in vandal-resistant enclosure	EA	1		
74	Backflow Preventer in vandal-resistant enclosure	EA	1		
75	Irrigation Control Wiring	LS	1		
76	Irrigation System	LS	1		
77	Hanging Baskets	LS	1		
78	Reset ATT Vault Manhole Frame and Grate	EA	3		
	Total Base Bid Amount				
Alternate One					
81	Deduct - Concrete Sidewalk - Stamped and Colored	SF	-1933		
82	Add- Brick Pavers on Slab (at Tree Wells)	SF	1933		
83	Add - Concrete Border	LF	211		
	Total Bid Alternate One				

DOWNTOWN IMPROVEMENT PROJECT – PHASE II
BID NO. 16-01
IN THE CITY OF LAKEPORT, CALIFORNIA
BID SCHEDULE
(Addendum No. 3)

The Contractor shall be responsible for calculating and providing unit prices for the bid schedule. The bid schedule shall include all costs for services, labor, materials, equipment, and installation associated with completing the work in place per the plans, specifications and details.

Base Bid Schedule Total: \$ _____

Base Bid Schedule Total (in words): _____

Bid Alternate One Bid Schedule Total: \$ _____

Bid Alternate Bid Schedule Total (in words):

(Company Name of Bidder)

(Date)